

NORDSTROM RACK – TURNKEY PROTOTYPE

SECTION 033536 – POLISHED CONCRETE FINISHING

- B. Do not begin installation until unsatisfactory conditions are resolved. Beginning work constitutes acceptance of site conditions and responsibility for defective installation caused by prior observable conditions.
- C. Concrete Surface:
 - 1. Clean, smooth, and flat conforming to specified floor tolerances specified by Section 035416.
 - 2. Free of chemicals, acids, curing compounds and other substances that may inhibit application of products specified by this section.
 - 3. New slabs must have cured for at least 28 days.
 - 4. Required Tests:
 - a. Measure pH according to method indicated in ASTM F 710. Notify the Architect of pH results lower than 8 and higher than 10.
 - b. Perform relative humidity test using in situ probes in accordance with ASTM F 2170. Notify the Architect of results higher than 75 percent.
 - c. Perform anhydrous calcium chloride test in accordance with ASTM F 1869. Notify the Architect of results higher than 8 pounds per 1000 square feet in 24 hours (MVER).
 - 5. Test results that are determined to be out of conformance with the polishing system manufacturer's acceptable limits shall be remedied to levels needed to attain warranty certification.
- D. Interior gypsum board and similar work capable of damaging work of this Section has been either completed or delayed until the final polish has been sealed and covered with protection material. Polish flooring prior to wall framing in BOH Office areas.

3.2 PREPARATION

- A. Clean concrete surfaces of dirt and other particulates and remove oil, stains, grease, adhesives, water repellants, and other substances that may be detrimental to work of this Section.
- B. Protect adjacent concrete surfaces not receiving the work of this Section.
- C. Dust Control: Seal off adjacent building areas and cover adjacent work to limit air-born dust migration from settling on surfaces and polluting other parts of building.
- D. Conform to the system manufacturer's instructions and provisions of the Contract Documents to achieve appearance conforming to accepted mock-ups.
- E. Polishing Overlay Topping (Optional):
 - 1. Mechanically prepare surface to ICRI CSP 3-5. Use of acid is prohibited.
 - 2. Clean and prime substrate, prior to pouring topping, in accordance with the topping manufacturer's installation instructions.

3.3 INSTALLATION

- A. Install polished concrete floor system in accordance with system manufacturer's instructions at locations indicated on the Drawings.
- B. Complete all joint filling work a minimum of 72 hours prior to commencement of any grinding or polishing. Fill movement joints and active cracks with semi-rigid joint sealant.
- C. Perform all polishing procedures to ensure a consistent appearance from wall to wall in accordance with established appearance criteria as approved in the mock-up.
- D. Clean floor thoroughly after each grinding pass using dust extraction equipment properly fitted with squeegee attachment or walk behind auto scrubber suitable to remove all visible loose debris and dust.

3.4 INITIAL GRINDING

- A. Begin grinding in one direction using sufficient size grit pad.